Sl. No.	Items of work	Quantity	Unit	Rate
				Rs. a. p.
	Alternative Items.			
8	Roofing with Madras terrace as per specifications with kappy concrete and two courses of flat tiles, bottom and top plastered with necessary slope for draining water	..	Sqrs.	35 0 0
9	Teakwood wrought and put up for joists with wood oiling, etc., complete	..	C.ft.	4 12 0

M. N. LAKSHMAN RAO,
Offg. *Executive Engineer.*

SHIMOGA DIVISION.

Abstract Notification dated the 24th May 1940.

The attention of the public is drawn to the notification calling for tenders for Restoring Kasagar Chittekere (Major Tank) feeder to Jodikere Register No. 592, Tirthahalli Taluk, published in pages 1228-1229, Part VI of the *Mysore Gazette*, dated 30th May 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 21st June 1940.

Earnest money required for the work is Rs. 190 which should be credited to the Treasury to 17(*a*) P. W. Deposits and challan enclosed.

Notification dated 27th May 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 24th June 1940, for dismantling the existing damaged building of the temple of Sri Somagodu Ramachandradevaru and constructing a new building at Tirthahalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four per form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 300 (three hundred only) credited to 17 (*a*) P. W. Deposits, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for dismantling the existing damaged building of the temple of Sri Somagodu Ramachandradevaru and constructing a new building at Tirthahalli in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposit.

Abstract estimate for the cost of dismantling the existing damaged building of the temple of Sri Samagodu Ramachandra Devaru and constructing a new building at Tirthahalli.

Item No.	Description of work	Unit	Rate	Quantity
	I. Front portions with up-stairs,		Rs. a. p.	
1	Earthwork excavating foundation—Front portion ..	C.yd.	0 4 0	75
2	Filling in foundation with lime concrete	C.ft.	0 4 0	404
3	Rough stone in mud filling foundation	,,	0 2 6	1,138
4	Size stone in mud for basement	,,	0 3 0	925
5	Burnt brick in mud	,,	0 2 9	3,640
6	Jungle wood doors with hinges, clamps, battened shutters, etc., complete	S.ft.	1 0 0	127
7	Main door with ornamental or brass knots with spikes 8″ apart	,,	1 4 0	48
8	Junglewood windows with iron bars, (6×10) battened shutters, hinges, etc., complete	,,	1 4 0	240
9	Burnt stone slabs 5″ to 6″ thick roughly dressed ..	,,	1 0 0	449
10	Teakwood wrought and put up	C.ft.	4 0 0	237
11	Teakwood ceiling plank 1¼″ thick	S.ft.	0 6 0	768
12	Roofing with Mangalore tiles on teak reepers making use of old available tiles	..	8 0 0	18·36
13	Ridge tiles set in mortar and cement pointed. Old tiles..	R.ft.	0 2 0	108
14	Cornice all round	,,	0 4 0	170
15	Mud plastering with whitewashing	Sqr.	1 0 0	52·78
16	Chunam pointing	,,	2 0 0	6·84
17	Flooring with gravel and cow-dung wash	C.yd.	1 0 0	12
18	Flooring the passage with burnt stone slabs including cement pointing	S.ft.	0 6 0	81
19	Flooring the top storey with gravel including cement plastering and colouring, etc.	Sqr.	10 0 0	8·00
20	Varnishing door and windows with paints	,,	4 0 0	7·82
21	Dismantling the existing structure and stacking the available and released materials and clearing, etc., complete	L. S.	..	..
	II. Rear portion of Sri Samagodu Ramachandra Devaru Temple.			
1	Earthwork excavation for foundation	C.yd.	0 4 0	149
2	Filling in foundation with rough stone in mortar ..	C.ft.	0 2 6	3,635
3	Size stone in mud	,,	0 3 0	1,197
4	Burnt brick in mud	,,	0 2 9	2,708
5	Burnt stone slabs dressed and fixed	S.ft.	0 4 0	454
6	Teakwood doors with battened shutters, iron fittings, etc., complete	,,	1 0 0	180
7	Teakwood windows with iron bars, battened shutters, iron fittings, etc., complete	,,	1 4 0	144
8	Teakwood wrought and put up including wood oiling ..	C.ft.	4 0 0	21,567
9	Roofing with Mangalore tiles on teak reepers	Sqr.	20 0 0	10·70
10	Roofing with old tiles over new reepers	,,	8 0 0	32·66
11	Ridge tiles set in mortar	R.ft.	0 8 0	64
12	Fixing old ridge tiles in mortar	,,	0 2 0	192
13	Mud plastering with cow-dung wash and white washing ..	Sqr.	1 0 0	52·53
14	Flooring with gravel with cow-dung wash, etc. ..	,,	1 0 0	18·51
15	Constructing steps with available stone slabs	No.	4 0 0	6
16	Dismantling the old structure	L. S.	..	..

Notification dated 1st June 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 29th June 1940, for restoring Balagar Kempa-Saruvinakere, Hullathi Village, Tirthahalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury chellan for Rs. 60, credited to "17 (a) P.W. Deposits" in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Balagar Kempasaruvinakere, Hullathi Village, Tirthahalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Eecutive Exngineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards security deposit.

Abstract estimate for restoring Balagar Kempasaruvinakere Minor Tank, S. No. 19 of Hullathi village, Tirthahalli Taluk.

Item No.	Description of work	Unit	Rate	Quantity
	Bund R. L. 55·00 top with 4½ slopes 2 : 1.		Rs. a. p.	
1	Cutting grips and trenches in the breached position removing debris, etc.	L. S.	..	..
2	Cutting grips to join old and new earth on the bund, jack bund, etc.	,,	..	..
3	Earthwork to bund with watering and consolidation. Earth to be got from tank bed	C.yd.	0 6 0	972
4	Providing puddle wall in the centre of breach including foundation, etc.	,,	1 0 0	10
5	Turfing the slopes of bund	Sqr.	0 12 0	104
6	Providing and fixing grade stones with figuring and painting, etc.	No.	2 8 0	3
7	Do Index stones	,,	1 0 0	3
8	Do B. M. stones	,,	4 8 0	2
9	Do Reg. No. and date stone	,,	10 0 0	1
10	Providing and fixing iron gauge plates one near the sluice and one near weir (gauges departmental supply) ..	,,	10 0 0	1

Item No.	Description of work	Unit	Rate	Quantity
	Construction of a C. I. pipe sluice of 3″ dia. cill 48·00.		Rs. a. p.	
1	Cutting open the bund and refixing the same with watering and consolidation	C.yd.	0 6 0	16
2	Earthwork excavation for foundation	,,	0 4 0	5
3	Providing rough stone in clay in case the foundation is found to be loose and slushy including earthwork excavation from 45·00 to 43·00	,,	3 0 0	3
4	Stone jelly concrete in cement mortar 1 : 4 : 8 ..	C.ft.	0 7 0	133
5	Size stone in cement mortar 1 : 5	,,	0 8 0	97
6	Stone jelly concrete in cement mortar 1 : 2 : 4 ..	,,	1 0 0	36
7	Burnt stone slabs 6″ thick dressed and fixed in cement mortar. Gibbet and guide slabs	S.ft.	0 12 0	36
8	Drilling holes in slabs	No.	1 0 0	2
9	Providing 3″ dia. R. C. C. pipes including fixing, etc., complete	R.ft.	1 0 0	36
10	Providing a junglewood platform from the bund to the sluice 2′ wide with wooden beams, slab support, etc...	No.	15 0 0	1
11	Providing and fixing T. wood plug with iron rod and locking arrangements, etc.	No.	10 0 0	1
12	Rough stone work revetment to front slope ..	C.yd.	2 8 0	24
13	Cement pointing and plastering to masonry, etc. ..	L. S.	..	..
	Waste Weir length 10′ R. L. 51·50.			
1	Earthwork excavation for foundation of body wall ..	C.yd.	0 4 0	3
2	Stone jelly concrete in cement mortar 1 : 4 : 8 for foundation of body wall	C.ft.	0 7 0	14½
3	Size stone in cement mortar 1 : 5 body wall	,,	0 8 0	32
4	Burnt stone slabs 6″ thick dressed and fixed in cement mortar with joints, coping slabs, etc.	S.ft.	0 12 0	47
5	Rough stone work revetment	C.yd.	2 8 0	19
	Miscellaneous Works.			
1	Clearing both thick and thin jungle on slopes of bund ..	L. S.	..	..
2	Excavating and clearing the check drain on the right side of the bund	C.yd.	0 4 0	33
3	Rough stone pitching to the halla at the bund portion ..	,,	2 8 0	22
4	Miscellaneous and unforeseen items	L. S.	..	..

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Notification dated 29th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 11 June 1940, for the work of construction and lay out of Bus Stand in Kadur Town.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur Division, on payment of annas four per each copy should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, in a sealed cover and superscribed as "Tender for the work of construction and ley out of Bus Stand in Kadur Town." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury challan of Rs. 290 (in words) rupees two hundred and ninety only for having credited the earnest money to 17 (*a*) P.W.D. Deposits. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest. Tenders unaccompanied by earnest money will not be accepted.